



SUPPLEMENTAL / BID BULLETIN

This Addendum is issued to modify or amend items in the Bid Document (*Philippine Bidding Documents*) for **Procurement of Works for the Construction of Masanag Diversion Dam/IB No. 2023-013(AMV)**.

On Philippine Bidding Documents:

Section VIII. Bill of Quantities

PROJECT TITLE: CONSTRUCTION OF MASANAG DD

LOCATION: Brgy. Masanag, Hamtic, Antique

Item No.	Scope of Works	Quantity	Unit	Unit Price (Php)	Amount (Php)
	GENERAL ITEM				
SPL1	Mobilization and Demobilization	1.00	lot		
SPL2	Temporary Facility	1.00	lot		
SPL3	Provision of Permanent Marker & COA Billboard and Signboard	1.00	lot		
SPL4	Diversion of water and care of creek	1.00	lot		
SPL5	Safety and Health	1.00	lot		
SPL6	Permit and Licenses	1.00	lot		
	Dam				
100(1)	Clearing and Grubbing	320.00	sq.m.		
102(1)	Common Excavation	90.00	cu.m.		
102(2)	Rock Excavation	320.00	cu.m.		
100(2)	Structural Backfill	156.00	cu.m.		
201	Levelling Course	32.00	cu.m.		
404	Reinforcing Bars	4400.00	kgs.		
405(1)	Concrete Class "A" (w/ Forms)	80.00	cu.m.		
504	Grouted Riprap	44.00	cu.m.		
	Weep Hole				
SPL6a	Perforated	6.00	l.m.		
SPL6b	Non-perforated PVC Pipe	4.00	l.m.		
505	Rubble Masonry	50.50	cu.m.		
713	Wooden Flashboard (Yakal) including DV & EC	20.00	Bd. ft		
SPL7	Trashrack and fishscreen	1.00	Ass.		
	Manhole, Division and desilting box				
102(1)	Common Excavation	20.91	cu.m.		
100(2)	Structural Backfill	14.75	cu.m.		
404	Reinforcing Bars	152.50	kgs.		
405(1)	Concrete Class "A" (w/ Forms)	5.00	cu.m.		
201	Levelling Course	3.10	cu.m.		
	Outlet and Canal Works				
102(1)	Common Excavation	133.00	cu.m.		
100(2)	Structural Backfill	125.00	cu.m.		
504	Slope Protection/Grouted Riprap	35.00	cu.m.		
404	Reinforcing Bars	3064.00	kgs.		
405(3)	Concrete Class "B" (w/ Forms)	44.68	cu.m.		
405(4)	Concrete Class "B" (w/o Forms)	41.00	cu.m.		
201	Levelling Course	45.00	cu.m.		
	TOTAL				

For guidance and information of all concerned.

JONIC F. NATIVIDAD, DVM
 BAC Chairperson