BILL OF QUANTITIES

Project Title:					
Brgy./Mun./Province					
Total Project Cost:					
Item No.	**Scope of Works**	**Quantity**	**Unit**	**Unit Price**	**Amount**
I.	**GENERAL REQUIREMENTS**				
SPL1	Project Signboard, COA Billboard, and Project Marker	1.00	lot		
B.9	Mobilization and Demobilization	1.00	lot		
II.	**EARTHWORKS**				
800(1)	Site Clearing and Grubbing	272.00	sq.m		
803(1)a	Structure Excavation, Common Soil	5.00	cu.m		
III.	**REINFORCED CONCRETE WORKS**				
900	Structural Concrete with RSB and Formworks	7.00	cu.m		
IV.	**MASONRY WORKS**				
1046(2)a1	CHB Non-load Bearing, 4" (including Reinforcing Steel)	36.00	sq.m		
1027(1)	Cement Plaster Finish	24.00	sq.m		
V.	**STEEL FRAMING WORKS**				
1047	Structural Steel	2,727.00	kg		
VI.	**PAINTING WORKS**				
1032(a)3	Steel Painting	2,727.00	kg		
VII.	**ROOFING AND COVERING WORKS**				
SPL2	PE Plastic, Insect Net Mesh, Shade Net, Weed Eliminator, and Other Accessories	1.00	lot		
VIII.	**HYDROPONIC SYSTEM**				
SPL3	PVC Tubes, PVC Pipes, PE Pipes, Fittings, Controller, Submersible Pump, Multi-fans, Cooling Pads, Aluminum Frames, Hydroponic Pots, Inputs and Fertilizers, and Other Accessories	1.00	lot		
				TOTAL	