



## BILL OF QUANTITIES

Item No.	Scope of Works	Quantity	Unit	Unit Price (Php)	Amount (Php)
<b>I. OTHER GENERAL REQUIREMENTS</b>					
1.0	TEMPORARY FACILITY	1.00	lot		
B.5	PROJECT SIGNBOARD , COA BILLBOARD and DA- WESTERN VISAYAS LOGO	1.00	lot		
B.7(2)	OCCUPATIONAL SAFETY AND HEALTH	1.00	lot		
B.9	MOBILIZATION/DEMOBILIZATION	1.00	lot		
B.3	PERMITS AND LICENSES	1.00	lot		
<b>II. SITE WORKS</b>					
800	SITE CLEARING and GRUBBING	303.69	sq.m.		
<b>III. EARTHWORKS</b>					
803a	STRUCTURE EXCAVATION	51.10	cu.m.		
804	STRUCTURAL BACKFILL AND EMBANKMENT	119.06	cu.m.		
<b>IV.PLAIN AND REINFORCED CONCRETE WORKS</b>					
900(1)a	STRUCTURAL CONCRETE (Footing )	12.02	cu.m.		
900(1) b	STRUCTURAL CONCRETE (Columns )	8.90	cu.m.		
900(1) c	STRUCTURAL CONCRETE (Beam)	23.01	cu.m.		
900(1) d	CONCRETE WORKS (Slab on Grade, Lavatory- Class "B",Stairs and Ramp )	29.12	cu.m.		
900(1) e	LEVELLING COURSE	28.60	cu.m.		
902(1)a	REINFORCING STEEL BAR (DEFORMED)	5266.00	kg		
903(2)a	FORMS AND SCAFFOLDING(FALSE WORK)	339.66	sq.m.		
<b>V. MASONRY WORKS</b>					
1027(1)	CEMENT PLASTER FINISH	610.29	sq.m.		
1046(2)	CHB (Including Reinforcing Steel)	289.76	sq.m		
<b>VI.FABRICATED MATERIALS</b>					
1008(1)	WINDOWS	1.00	lot		
1010	DOOR	1.00	lot		
<b>VII. PAINTING WORKS</b>					
1032(1)a	PAINTINGS(Concrete structures including Polyurethane floor finish)	601.87	sq.m.		
1032(1)b	PAINTINGS(Steel)	271.30	sq.m.		
<b>VIII. ROOF AND ROOF FRAMING WORKS</b>					
1003(1)a1	CEILING WORKS	246.30	sq.m.		
1047	Structural Steel(Roof framing and Hand Rails)	251.54	sq.m.		
1014(1)bl	Pre- Painted Metal Sheets,longspan and other bended Accessories	251.54	sq.m.		
<b>IX. ELECTRICAL WORKS</b>					
1100	ELECTRICAL	1.00	lot		
<b>X. PLUMBING/ SANITARY WORKS</b>					
1002	PLUMBING	1.00	lot		
<b>XI. SEPTIC TANK</b>					
1001(11)	SEPTIC TANK(CHB WITH REINFORCING BARS)	1.00	lot		
1018	TILE WORKS	1.00	lot		
<b>XII. CARPENTRY WORKS</b>					
1003(2)a1	CARPENTRY AND JOINERY WORKS	42.66	sq.m.		
1035	NON-STRUCTURAL METAL FRAMING	119.90	m		
<b>TOTAL</b>					