Project Title: Procurement of Labor and Materials for the Repair of DC-70 Rice Combine Harvester
Location: DA-WESVIARC, Hamungaya, Buntatala, Jaro, Iloilo City

1	**Kubota DC70 Rice Combine Harvester Serial No. PH 507859**	**1**	**lot**		
	Particulars/Description	**Quantity**	**Unit**	**Unit Price (Php)**	**Total Amount (Php)**
	1.A. Materials:				
	Rubber crawler, 500-90*53 (DC-70), 5T078-2312-0	2	pcs	70,000.00	**140,000.00**
	Battery (DC-70)	1	pcs	12,000.00	**12,000.00**
	Finger shaft guide, 5T051-5245-0	18	pcs	180.00	**3,240.00**
	Threshing Belt (DC-70, 2pcs/set)	1	set	14,836.00	**14,836.00**
	Travelling Belt (DC-70, 2pcs/set)	1	set	15,965.00	**15,965.00**
	Shaft Clutch Assembly, 5T054-1610-3	1	set	30,000.00	**30,000.00**
	Plate Friction Lining, 5H493-1754-0	1	set	24,500.00	**24,500.00**
	Gasket, transmission 5T051-1648-0	1	set	6,000.00	**6,000.00**
	Oil Seals, T0070-1509-0	2	pcs	250.00	**500.00**
	Oil Seals, 58813-1645-0	2	pcs	250.00	**500.00**
	Bearing, Ball T1150-2245-0	2	set	1,000.00	**2,000.00**
	Bearing, Needle 44512-2364-0	2	set	1,250.00	**2,500.00**
	Bearing 5H491-1632-0	2	set	1,000.00	**2,000.00**
	Bearing, Ball 08141-06208	2	set	1,000.00	**2,000.00**
	Bearing, Roller H3680-4003-0	2	set	1,000.00	**2,000.00**
	UDT oil	1	pails	7,500.00	**7,500.00**
	Engine Oil Filter	1	pcs	2,500.00	**2,500.00**
	Hydraulic Filter	1	pcs	6,000.00	**6,000.00**
		Total			**274,041.00**
	1.B. Labor				
	1. Provision of hauling truck to transport DC-70 combine harvester to and from the repair shop.				**2,750.00**
	2. Repair works including dismantling of unit, removing and replacing of damaged parts (transmission bearing, roller bearing, ball bearing, shaft clutch assembly, plate friction lining, shaft clutch assembly gear and overhauling gasket of transmission case). Removing and replacing rubber track crawler, finger shaft guide, battery, threshing and travelling belts. Conduct change oil, replacing engine oil filter and hydraulic filter.				**20,000.00**
	3. Testing and commissioning the performance and functionality of DC-70 combine harvester.				**3,000.00**
		Total			**25,750.00**
			Total Project Cost		**299,791.00**

Prepared by:

LYKA M. HISU-AN
Science Research Assistant

Reviewed by:

ENGR. FLERIDA A. DEMAMAY
Senior SRS