



3	JICA SEED PROCESSING PLANT FACILITY (Repair of Gutter System)			55.00	ln.m.		
	3.A. Materials:						
	Pre-painted Standard A-style Box Gutter GA 24 (0.701mm-thick) 8"x 12" (WxH)		55	ln.m.			
	End Cap		8	pcs			
	Water Sealant		15	tubes			
	Gutter Accessories (including under brackets, hanger, gutter screws, gutter straps, etc.)		1	lot			
	Blind Rivets 1/8" x 3/8"		5	box			
	PVC Pipe 4.0"Ø Series 1000, 3m		40	lengths			
	Elbow 90°		48	pcs			
	Downspout Wall Bracket 4"Ø		96	pcs			
	Solvent Cement 400cc		10	cans			
	Drill Bits, assorted		4	pcs			
			Total				
	3.B. Labor						
	1. Clearing of work area.		16	man-days			
	2. Removing of existing gutter system (see attached gutter system layout).						
	3. Installation of gutter and downspouts						
	4. Sealing and finishing.						
			Total				
4	JICA Dryer and Seed Processing Plant			1	lot		
	1.A. Materials:						
	Particulars/Description	Quantity	Unit				
	V-Belt, B142	5	pcs				
	V-Belt, B132	5	pcs				
	V-Belt, B44	2	pcs				
	V-Belt, B42	4	pcs				
	V-Belt, B33	2	pcs				
	V-Belt, A44	12	pcs				
	V-Belt, A49	12	pcs				
	V-Belt, C62	6	pcs				
	Ignition Transformers						
	Specifications:	5	pcs				
	Capacity:						-
	Primary Coil:						-
	Secondary Coil:						-
	Frequency:						
	Phase:						
	Ignition Coil						
	Specifications:	5	pcs				
	Voltage:						
	Frequency:						
	Pressure:						
	Orifice:						
	Sol. Valve:						
	Fuel Hose						
	Specifications:	10	pcs				
	Length:						
	Hose Diameter:						

	Material:	Braided fuel hose, reinforced rubber and steel wire					
	1.B. Labor						
	Dismantling of damaged parts and installation of replacements.						