



PROJECT TITLE: ESTABLISHMENT OF BAYUYAN SPIS
LOCATION: Brgy. Bayuyan, President Roxas, Capiz

BILL OF QUANTITIES

Item No.	Scope of Works	Quantity	Unit	Unit Price (Pnp)	Amount (Pnp)
SPL1	TEMPORARY FACILITY	1.00	lot		
B.16 & B.5	PROJECT MARKER & SIGNBOARD/BILLBOARD (1-4'x8' and 1-8'x8')	1.00	lot		
B.9	MOBILIZATION/DEMOBILIZATION	1.00	lot		
B.7 (2)	OCCUPATIONAL SAFETY AND HEALTH	1.00	lot		
I	SOLAR PUMP/ARRAY/MOUNTING STRUCTURE				
803	STRUCTURE EXCAVATION (FOR FOUNDATION/PEDESTAL)	2.09	m3		
1708	LEVELLING COURSE	0.40	m3		
404	REINFORCING STEEL BARS	128.46	kg		
414	FORMWORKS	15.36	m2		
405	CONCRETE FOUNDATION/PEDESTAL (Class B)	1.92	m3		
1705	STRUCTURE BACKFILL	1.50	m3		
i	SOLAR POWER MODULE MOUNTING STRUCTURE	1.00	lot		
2	SOLAR POWER MODULES (Mono-crystalline-5,500 watt-peak)	1.00	lot		
3	INVERTER & CONTROLLER - 4 KW	1.00	unit		
4	SOLAR PUMP (SUBMERSIBLE) - 4 hP	1.00	unit		
5	INVERTER & CONTROLLER BOX	1.00	lot		
II	ELEVATED TANK				
803	STRUCTURE EXCAVATION	1.44	m3		
405	CONCRETE WORKS (Class A)	0.72	m3		
404	REINFORCING STEEL BAR	94.32	kg		
SPL2	STORAGE TANK METAL FRAME	1.00	lot		
1201 (8), 1602 & 1603	INSTALLATION OF WATERTANK , PIPES, VALVES & FITTINGS	1.00	lot		
1705	STRUCTURAL BACKFILL	0.72	m3		
TOTAL					