Republic of the Philippines
DEPARTMENT OF AGRICULTURE
Western Visayas
Iloilo City

BILLS OF QUANTITIES

Project Title		IMPROVEMENT OF EXISTING CHICKEN HOUSE			
Brgy./Mun./Province		BRGY. CODINGLE, DUMARAO, CAPIZ			
Item No.	Scope of Works	Qty	Unit	Price	Total
I. OTHER GENERAL REQUIREMENTS					
B.1	Project Signboard, Billboard	1.00	lot		
II. EARTHWORKS					
800(1)	Clearing and Grubbing	1.00	lot		
801(1)	Removal of Structures and Obstruction	40.00	sqm		
803.0	Structural Excavation	4.00	cu.m		
804.0	Backfill and Embankment (Gravelfill/Earthfill, Compacted)	2.00	cu.m		
III. PLAIN AND REINFORCED CONCRETE WORK					
900(7)	Reinforced Concrete (Wall footing, including rebar)	2.00	cu.m		
III. FINISHINGS AND OTHER CIVIL WORKS					
1046(2)a1	CHB Non Load Bearing (including Rebar and Mortar)	29.00	sqm		
1047(2)a	Structural Steel (framings for doors, windows, walls, cages)	563.00	kgs		
1003(22)	Modular Partition (including metal studs, welded wire mesh, net, plastic chicken wire mesh, GI sheet)	430.00	sqm		
		TOTAL			