



PROJECT TITLE:ESTABLISHMENT OF BAKHAW NORTE SPIS
LOCATION:Brgy. Bakhaw Norte, Kalibo, Aklan

BILL OF QUANTITIES

Item No.	Scope of Works	Quantity	Unit	Unit Price (Php)	Amount (Php)
SPL1	MOBILIZATION/DEMOBILIZATION	1.00	lot		
SPL2	PROJECT MARKER & SIGNBOARD/BILLBOARD (1-4'x8' and 1-8'x8')	1.00	lot		
A	WELL CONSTRUCTION WITH PUMPING TEST	1.00	lot		
B	MOUNTING STRUCTURES, SOLAR MODULES, INVERTERS & CONTROLLER AND PUMP				
803	STRUCTURE EXCAVATION (FOR FOUNDATION/PEDESTAL)	1.40	cum		
1707	GRAVEL BEDDING	0.20	cum		
404	REINFORCING STEEL BARS	105.91	kg		
414	FORMWORKS	6.72	sqm		
405	CONCRETE WORKS (CLASS B)	0.55	cum		
403	SOLAR POWER MODULE MOUNTING STRUCTURE	1.00	lot		
1	SOLAR POWER MODULES (5,500WP-minimum)	14.00	unit		
2	INVERTER & CONTROLLER - (5.5 KW minimum)	1.00	lot		
3	SOLAR PUMP (Submersible-5HP minimum)	1.00	unit		
C	ELEVATED TANK , PIPES, FITTINGS AND VALVES				
803	STRUCTURE EXCAVATION	1.22	cum		
405	CONCRETE WORKS- Class A	0.72	cum		
404	REINFORCING STEEL BAR	82.10	kg		
403	STORAGE TANK METAL FRAME	1.00	lot		
1602/1603	INSTALLATION OF WATERTANK , PIPES, VALVES, FITTINGS & OTHER ACCESSORIES	1.00	lot		
1601	STRUCTURAL BACKFILL	0.54	cum		