

Republic of the Philippines
DEPARTMENT OF AGRICULTURE
Western Visayas

BILL OF QUANTITIES

Project Title:		UPGRADING OF GOAT HOUSE			
Category:		Upgrading			
Brgy./Mun./Province		WESVIARC, Hamungaya, Brgy. Buntatala, Jaro, Iloilo City			
Source of Fund/Year		Department of Agriculture			
Implementation Mode:		By Contract			
Project Description:Upgrading of Goat House (Reinforce Concrete Works, Roof framing and Cladding, Plumbing works)		Project Duration:		51 CD	
		Equipment Needed:		Welding machine	
		Technical Personnel:		Foreman	
				Skilled Worker	
				Unskilled Worker	
Item No.	Scope of Works	Quantity	Unit	Unit Cost	Total
PART I	GENERAL REQUIREMENTS				
1.1	SIGNBOARD/BILLBOARD (1-4'x8' and 1-8'x8')	1.00	lot		
1.2	CONSTRUCTION SAFETY & HEALTH	1.00	lot		
1.3	MOBLIZATION/DEMObILIZATION	1.00	lot		
PART II	UPGRADING OF GOAT HOUSE	-			
2.1	DEMOLITION WORKS	1.00	lot		
2.2	CLEARING & LAYOUT	150.00	sq.m		
2.3	EXCAVATION	2.00	cu.m		
2.4	BACKFILLING (Compacted)	1.00	cu.m		
2.5	REINFORCING STEEL BARS	211.00	kg		
2.6	FORMWORKS & FALSE WORK	1.00	lot		
2.7	CONCRETE WORKS	2.00	cu.m		
2.8	FLOOR JOIST, SLOTTED FLOORING, STAIR & FEEDING TROUGH	2,270.00	bd ft		
2.9	METAL PAINTING	1.00	lot		
2.10	RAILINGS & CLOSURE	24.00	l.m		
2.11	ROOF FRAMING	843.00	kg		
2.12	ROOF CLADDING & BENDED ACCESSORIES	60.00	sq.m		
2.13	PLUMBING WORKS	1.00	lot		
2.14	ELECTRICAL WORKS	1.00	lot		
PART III	ELEVATED TANK EXTENSION	-			
3.1	METAL FRAME EXTENSION	1.00	lot		