



Republic of the Philippines
DEPARTMENT OF AGRICULTURE WESTERN VISAYAS
 Hamungaya, Brgy. Buntatale, Jaro, Iloilo City
 westernvisayas@mail.da.gov.ph | (033) 336-4221

BILL OF QUANTITIES

Project Title: Establishment of Brgy. Paticut Solar Powered Irrigation System (SPIS)
 Location: Brgy. Paticut, Hinigaran, Negros Occidental

Item No.	Scope of Works	Quantity	Unit	Unit Price	Total
A	Temporary Facility/Field Office				
A.1.1 (5)	Provision of Temporary Facility (Rental Basis)	1.00	lot		
B.	GENERAL REQUIREMENTS				
B.1	Project Billboard, Marker, Signboard & COA Billboard	1.00	lot		
B.2	Mobilization/Demobilization	1.00	lot		
C.	DRILLING WORKS				
C.1	Well Construction (with groundwater/pumping test)	1.00	lot		
D.	SOLAR MOUNTING STRUCTURES AND ACCESSORIES				
D.1	Structural Excavation	3.39	cu.m		
D.2	Structural Backfill	0.40	cu.m		
D.3	Leveling Course	0.22	cu.m		
D.4	Reinforcing Steel Bars	105.16	kgs		
D.5	Formworks	7.68	sq.m		
D.6	Concrete Works (Class A)	0.73	cu.m		
D.7	Solar Power Module Mounting Structure (with Inverter cage)	1.00	lot		
D.8	Solar Power Module (6000 Wp, Minimum)	1.00	lot		
D.9	Inverter and Controller 5.5 KW w/ accessories	1.00	unit		
D.10	Submersible Pump (5hp)	1.00	unit		
D.11	Pipes Fittings and Other Accessories	1.00	lot		
E.	ELEVATED TANK				
E.1	Structural Excavation	4.80	cu.m		
E.2	Structural Backfill	2.78	cu.m		
E.3	Leveling Course	0.26	cu.m		
E.4	Reinforcing Steel Bars	93.62	kgs		
E.5	Formworks	7.68	sq.m		
E.6	Concrete Works Class A	1.24	cu.m		
E.7	Tank Post and Frame, Water Tank	1.00	lot		
		TOTAL			