



Republic of the Philippines
DEPARTMENT OF AGRICULTURE
Western Visayas
Iloilo City

PROJECT TITLE: ESTABLISHMENT OF DASAL SPIS
LOCATION: Brgy. Dasal, Sibunag, Guimaras

BILL OF QUANTITIES

Item No.	Scope of Works	Quantity	Unit	Unit Price (Php)	Amount (Php)
I GENERAL ITEM					
SPL1	TEMPORARY FACILITY (Rental Basis)	1.00	lot		
SPL2	PROJECT MARKER & SIGNBOARD/BILLBOARD (1-4'x8' and 1-8'x8') and Project Marker	1.00	lot		
SPL3	MOBILIZATION / DEMOBILIZATION	1.00	lot		
II POWER HOUSE					
803	STRUCTURE EXCAVATION	12.64	cum		
1707	GRAVEL BEDDING	0.40	cum		
404	REINFORCING STEEL BARS	605.51	kg		
414	FORMWORKS	36.23	sqm		
405	CONCRETE WORKS (Class A)	4.50	cum		
1046	MASONRY WORKS	13.14	sqm		
1027	PLASTERING	38.18	sqm		
1006	PRE-FABRICATED DOOR	1.00	lot		
1601	STRUCTURE BACKFILL	2.40	cum		
III MOUNTING STRUCTURES, SOLAR MODULES, INVERTERS & CONTROLLER AND PUMP					
803	STRUCTURE EXCAVATION	0.75	cum		
1707	GRAVEL BEDDING	0.13	cum		
404	REINFORCING STEEL BARS	146.09	kg		
414	FORMWORKS	16.80	sqm		
405	CONCRETE WORKS (CLASS B)	0.88	cum		
SPL4	SOLAR POWER MODULE MOUNTING STRUCTURE	1.00	lot		
SPL5	SOLAR POWER MODULES (9900WP-minimum)	1.00	lot		
SPL6	INVERTER & CONTROLLER - (7.5KW minimum)	1.00	unit		
SPL7	SOLAR PUMP (SURFACE, 7.5HP)	1.00	unit		
IV ELEVATED TANK					
803	STRUCTURE EXCAVATION	1.58	cum		
404	REINFORCING STEEL BAR	117.21	kg		
405	CONCRETE WORKS- Class A	1.33	cum		
403	STORAGE TANK METAL FRAME	1.00	lot		
1201 (8)	INSTALLATION OF WATER TANK, PIPES, VALVES & FITTINGS	1.00	lot		
1601	STRUCTURAL BACKFILL	0.25	cum		
TOTAL					